



ADDENDUM NO. 2

Dated: January 8, 2013

JAMESTOWN CRESCENT CULVERT REPLACEMENT

Except as may be otherwise described, bidding requirements, materials, and workmanship for the work described herein shall conform to all requirements of the original Contract Documents. The following Addendum to the drawings and specifications are made a part of the project and takes precedence over the section of the specifications, in part, and/or drawings, as originally written.

This Addendum consists of four (4) pages.

<u>ITEM NO.</u>	<u>DESCRIPTION</u>
------------------------	---------------------------

1.	SPECIFICATIONS; Form of Bid; Pages 1.3-9 and 1.3-10
-----------	--

Remove: Pages 1.3-9 and 1.3-10

Replace with: Pages 1.3-9 (Addendum No. 2) and 1.3-10 (Addendum No. 2)

Summary:

- a. Item #2: Revised description
- b. Item #3: Revised description
- c. Item #6: Revised description
- d. Item #10: Revised description
- e. Item #12: Revised description
- f. Item #15: Revised description
- g. Item #17: Revised description
- h. Item #18: Revised description
- i. Item #21: Revised description
- j. Item #22: Revised description

2.	QUESTIONS AND ANSWERS
-----------	------------------------------

Question #1: Please verify the statement “Maximum Sound Pressure Levels shall not exceed 57db(A)...”

Answer #1: Due to the close proximity of the project site to residential properties, the exception will not apply, and maximum Sound Pressure Levels must be maintained.



City of Norfolk

Question #2: Please clarify the statement “Construction joints will not be permitted.”

Answer #2: Locate joints to least impair strength. Continue reinforcement across joints unless otherwise indicated. Final joint locations are subject to the approval of the Engineer or substantiating calculations from the Contractor.

Question #3: Please clarify the statement “All temporary sheeting and shoring shall be included in line item No. 9.” Line Item 10, “Structure with Wingwalls” appears to be a more practical choice.

Answer #3: Section 01270, Page 5, Note 21 shall be replaced with the following: “Steel Sheet Piles – Measurement will be made in TONS and include labor, material, equipment, disposal fees and all appurtenances that are necessary for installation of the steel sheet piles (permanent) in accordance with the contract drawings and specifications. All temporary sheeting and shoring shall be included in line item No. 10.”

Question #4: Drawing GI-004 indicated that on the second paragraph under “Verizon Fiber Optic Duct Bank” references the “south side of Kimball Terrace”. Please verify.

Answer #4: The second paragraph under “Verizon Fiber Optic Duct Bank” on Drawing GI-004 shall be replaced with the following: “The contractor shall be responsible for coordinating all activities with Verizon for work in close vicinity of the existing fiber optic duct bank located on the west side of Jamestown Crescent. The contractor shall provide written notice to Verizon no less than 4 weeks prior to starting demolition within this area so proper coordination of Verizon’s crews can be assigned”.

Receipt of this addendum shall be acknowledged on page 1.3-1 of the Bid Form

Prepared by: Jousha Hill, P.E.
Moffatt & Nichol

Christine Atkinson, P.E.
City of Norfolk

Issued by: Toni Fralich
Contract Monitoring Specialist

SCHEDULE OF UNIT PRICES
MAJESTIC AVENUE SIDEWALK & STREET IMPROVEMENTS
OWNER: CITY of NORFOLK, VIRGINIA

The unit prices have been computed in accordance with Paragraph 7.3.3.2 of the General Conditions of the Contract. Bidder acknowledges that estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all Unit Price Bid items will be based on actual quantities provided, determined as provided in the Contract Documents. The prices quoted shall include, without exception, all materials, labor, equipment, appliances, clean-up, applicable sales, use and other taxes, building permits or fees, and the Contractor's labor, overhead, profit, mobilization and other mark-ups, and in full accordance with the Specifications. Include allowance for waste where appropriate. The unit prices shall be maintained throughout the contract period. Unit prices shall be used in determining additions or deductions from the TOTAL CONTRACT AWARD amount in the event of changes in the work.

Item #	Description	Unit	Qty	Price	Extension
1	Mobilization / Demobilization	LS	1		
2	Storm Water Line Demolition	LS	1		
3	Water Main Line Demolition	LS	1		
4	Sidewalk Demolition	SF	517		
5	Curb & Gutter Demolition	LF	195		
6	Asphalt Demolition	SY	950		
7	Culvert & Miscellaneous Demolition	LS	1		
8	Grading	LS	1		
9	Rip Rap	TON	150		
10	Culvert with Wingwalls	LS	1		
11	15" RCP Storm Water Pipe	LF	11		
12	Storm Water Curb Inlet	EA	1		
13	Sidewalk Installation	SF	337		
14	Curb & Gutter Installation	LF	195		
15	Aggregate Base Material	CY	70		
16	Asphalt (BM-25)	TON	40		
17	Asphalt (SM-9.5)	TON	125		
18	12" Water Main & Fittings	LF	212		
19	Butterfly Valve	EA	1		

Attachment A-1

Item #	Description	Unit	Qty	Price	Extension
20	Waterline Service with Meter	EA	1		
21	Steel Sheet Piles	TON	7		
22	Miscellaneous	LS	1		
	TOTAL BID				

CONTRACTOR'S PRINTED NAME

CONTRACTOR'S SIGNATURE

Attachment A-2