



ADDENDUM NO. 3

Dated: January 14, 2013

JAMESTOWN CRESCENT CULVERT REPLACEMENT

Except as may be otherwise described, bidding requirements, materials, and workmanship for the work described herein shall conform to all requirements of the original Contract Documents. The following Addendum to the drawings and specifications are made a part of the project and takes precedence over the section of the specifications, in part, and/or drawings, as originally written.

This Addendum consists of four (4) pages.

<u>ITEM NO.</u>	<u>DESCRIPTION</u>
------------------------	---------------------------

1.	SPECIFICATIONS; Form of Bid; Pages 1.3-9 (Addendum No. 2)
-----------	--

Delete: "MAJESTIC AVENUE SIDEWALK & STREET IMPROVEMENTS"

Replace with: "JAMESTOWN CRESCENT CULVERT REPLACEMENT"

2.	TECHNICAL SPECIFICATIONS; Section 01010; Page 1 (Addendum No. 1)
-----------	---

Remove: Section 01010 – Page 1 (Addendum No. 1)

Replace with: Section 01010 – Page 1 (Addendum 3)

3.	TECHNICAL SPECIFICATIONS; Section 01270; Page 5
-----------	--

Remove: Section 01270 – Page 1

Replace with: Section 01270 – Page 1 (Addendum 3)

4.	QUESTIONS AND ANSWERS
-----------	------------------------------

Question #1: We have concerns over the sound level requirements as written in the specifications.

Answer #1: The construction noise exception will apply between 7:00 a.m. and 10:00 p.m. Maximum Sound Pressure Levels shall not exceed 52 db(A) between 10:00 p.m. and 7:00 a.m.

Receipt of this addendum shall be acknowledged on page 1.3-1 of the Bid Form



City of Norfolk

Prepared by: Jousha Hill, P.E.
Moffatt & Nichol

Christine Atkinson, P.E.
City of Norfolk

Issued by: Toni Fralich
Contract Monitoring Specialist

SECTION 01010

SUMMARY OF WORK

PART 1 - GENERAL

1.1 PROJECT DESCRIPTION

The project includes the replacement of the existing concrete box culvert with a new concrete box culvert and miscellaneous site work. The existing box culvert will be demolished. The construction also includes temporary closure of Jamestown Crescent, relocation of utilities, earthwork, replacement of asphalt pavement, replacement of sidewalk, installation of a new bike lane, installation of a retaining wall and site restoration.

1.2 PROJECT LOCATION

The project is located on Jamestown Crescent between Bolling Avenue and Magnolia Avenue.

1.3 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Contractor shall furnish the labor, materials, equipment and supplies to perform all Work specified and/or required to complete the project in accordance with the contract documents.
- B. Contractor's Duties: Unless specifically noted, the Contractor shall provide and pay for:
 - 1. Labor, materials, and equipment.
 - 2. Tools, construction equipment and fuel.
 - 3. Water and utilities required.
 - 4. Freight, sales tax, and building permit fees.

1.4 USE OF THE PREMISES

- A. All work shall be within the limits of construction shown on the plans.
- B. Contractor is responsible to correct all collateral damage to existing conditions caused by his work.
- C. The respective utility owners shall approve utility outages and shutdowns.
- D. The Contractor shall make provisions for maintaining two way vehicular traffic at all times on Bolling Avenue, immediately adjacent to the work area.
- E. All noise created by construction activity shall comply with the provisions of the Norfolk, Virginia, Code of Ordinances, Code of the City, Chapter 26 – Noise. The exception for construction equipment shall apply between 7:00 a.m. and 10:00 p.m. only. Maximum Sound Pressure Levels shall not exceed 52 db(A) between 10:00 p.m. and 7:00 a.m.

- 1.) Dewatering
- 2.) Excavation
- 3.) Disposal of surplus and unsuitable materials
- 4.) Test pits in advance of pipe laying
- 5.) Temporary shoring and bracing
- 6.) Backfilling, compacting, and compaction testing
- 7.) Furnish and install water main and fittings
- 8.) Flushing and testing
- 9.) Water for testing
- 10.) Removal of existing piping where required
- 11.) Pipe Bedding and Stone Backfill
- 12.) Tie into existing line
- 13.) Transition/adaptor fittings for joining dissimilar pipe materials
- 14.) Joints, elbow and etc.

19. Butterfly Valve

Measurement will be made based on **EACH** valve installed and satisfactorily tested.

20. Waterline Service Line with Meter, installed complete in place.

- a. Measurement will be made based on **EACH** service line installed and satisfactorily tested in accordance with the plans and specifications.

21. Steel Sheet Piles – Measurement will be made in **TONS** and includes labor, material, equipment, disposal fees and all appurtenances that are necessary for installation of the steel sheet piles (permanent) in accordance with the contract drawings and specifications. All temporary sheeting and shoring shall be included in line item No. 9.

22. Miscellaneous

Payment to be made for this item is paid on a **LUMP SUM BASIS** and includes labor, material, equipment, disposal fees and all appurtenances that are necessary for the remainder of the work associated with project in accordance with the contract drawings and specifications. Work shall include but not be limited to the following: traffic control, erosion and sediment control, temporary utility relocation, private and public utility coordination and over site, tree planting, earthen berm for water line, pavement markings, guardrail, site restoration and clean-up in accordance with the plans and specifications.

PART 2 – PRODUCTS

NOT USED

PART 3 – EXECUTION

NOT USED

END OF SECTION