



DISTRIBUTION SYSTEM SUPPLY

PIPELINE BEING CHLORINATED AND TESTED

NOTES:

1. ALL VALVES TO BE 2" BALL VALVES.
2. ALL PIPING SHALL BE PROTECTED FROM THE WEATHER DURING FREEZING CONDITIONS.
3. BACKFLOW PREVENTER SHALL BE INSTALLED AND TESTED IN ACCORDANCE WITH THE LOCALITY'S APPROVED CROSS CONNECTION CONTROL PROGRAM.
4. THE RPZ SHALL NOT BE INSTALLED IN A PIT OR AREA SUBJECT TO FLOODING.

**TEMPORARY MANIFOLD FOR
TEST AND CHLORINATION**

NOT TO SCALE

REFERENCE (NONE)	CATEGORY WATER DISTRIBUTION	DATE 6/16	SHEET No. 1 OF 1	DETAIL No. WD_09
---------------------	--------------------------------	--------------	---------------------	---------------------